

Description		Qty	Unit	Rate	Amount
<u>(23) FLOORS</u>					
<u>CONCRETE WORK</u>					
PRECAST CONCRETE					
<b>Precast concrete wide slab floor units; include hoisting units into position; all in accordance with the Architects &amp; Engineers drawings and specification, to contractors design to meet loads specified by Engineer, to include intumescent filling between units; all necessary temporary supports and propping as required, to include all fixings, dowel bars, drilling, shelf supports etc required to install floor units; all in accordance with Engineers drawings and specification</b>					
<b>Floors</b>					
150mm thick slab		65	m2	40.00	2,600.00
IN SITU CONCRETE					
<b>Concrete fill; 35N10</b>					
<b>Other Items - Edge Beam Infill</b>					
<b>cross sectional area not exceeding 0.10 sq m ; fill voids behind pre-cast units; allow for tying reinforcement to screed</b>		3	m3	175.00	525.00
<b>Prepare and apply 75mm concrete screed (for underfloor heating system); Easycreed or equal; all in accordance with the Engineers drawings and specifications</b>					
<b>Floors</b>					
exceeding 300mm wide		65	m2	22.00	1,430.00
SUNDRIES					
<b>Surface finishes</b>					
powerfloating		65	m2	3.00	195.00
<b>Insulation</b>					
50mm as per Architects specification		65	m2	12.00	780.00
Clonlea Lodge Rev.1 Budget Estimate 10.05.16 Prepared by E.D. Estimating		BQ/13		To Collection €	5,530.00

Description		Qty	Unit	Rate	Amount
<u>(23) FLOORS (Cont)</u>					
<u>(Cont) CONCRETE WORK</u>					
<u>(Cont) SUNDRIES</u>					
<b>Polythene</b>					
Standard 1200g		65	m2	2.00	130.00
FORMWORK					
<b>Formwork generally</b>					
<b>Edges of suspended slabs and landings; to screed</b>					
250 - 500 high		33	item	14.00	462.00
REINFORCEMENT					
<b>Bar; links or the like</b>					
H10 L Bar perimeter ties		0.5	t	995.00	497.50
Clonlea Lodge Rev.1 Budget Estimate 10.05.16 Prepared by E.D. Estimating		BQ/14		To Collection €	1,089.50